

1 - 100AT, 100AF, 2P, 240V, 22KAIC																			
3 - 15AT, 60AF, 2P, 240V, 10KAIC	1	assy.																	
4 - 20AT, 60AF, 2P, 240V, 10KAIC																			
3 - 30AT, 60AF, 2P, 240V, 10KAIC																			
2 - 40AT, 60AF, 2P, 240V, 10KAIC																			
All SQUARE D																			
Copper plate (600mm x 600mm x 3.16mm)	1	pcs.																	
Copper flat bar (3mm x 30mm)	7	mtrs.																	
20mmØ G.I. pipe Sc40	1	lm.																	
Sand	0.5	cu.m																	
Earthing Compound	3	pcs.																	
Cement	1	bag																	
Funel 6" w/ mesh wire	1	assy.																	
Consumables (tox, screws, bolt and nut)	1	lot																	
Sub-Total																			
B. Masonry Works/plastering																			
6 x 8 x 16 CHB	1847	pcs																	
Cement	185	bags																	
Screened Sand	35	cu.m																	
Wash gravel	30	cu.m.																	
deformed steel bars 10mm dia.	45	pcs																	
Tie Wire # 16	10	kg																	
Sub-Total																			
C. Footing foundation 1.20mx1.2mx.30m=4 cu.m.																			
Cement	40	bags																	
Screened Sand	2	cu.m																	
3/4 Gravel	4	cu.m																	
16 mm dia. Deformed	24	pcs																	
#16 G.I. Tire Wire	9	kgs																	
Sub-Total																			
D. For Columns post @ .3mx.25mx5.1m =3.44 cu.m																			
Cement	35	bags																	
Screened Sand	2	cu.m																	
3/4 Gravel	3	cu.m																	
16 mm dia. Deformed	54	pcs																	
10 mm ø x 6 m. DSB	66	pcs																	
#16 G.I. Tire Wire	9	kgs																	
Sub-Total																			
E beams @ .2mx.40mx60m=4.8cu.m.																			
Cement	48	bags																	
Screened Sand	3	cu.m																	
3/4 Gravel	5	cu.m																	
16 mm dia. Deformed	60	pcs																	
10 mm ø x 6 m. DSB	80	pcs																	
#16 G.I. Tire Wire	9	kgs																	
Sub-Total																			
F Tie beams .20mx.40mx48m=3.84cu.m.																			
Cement	39	bags																	
Screened Sand	2	pcs																	
3/4 Gravel	4	pcs																	

40
2
3.6

34.4
1.72
3.096

48
2.4
4.32

38
1.9
3.42

latex t/t color toludine red	1	lit												
latex t/t lamp black	1	lit												
latex t/t color raw siena	2	lit												

Sub-Total

Total