PROJECT DESCRIPTION AND SCOPE OF WORK ILOILO ACCESS ROAD

Project Title: PROPOSED IMPROVEMENT AND ACCESS ROAD CONCRETING

Locatio : PAGASA RADAR AND SYNOPTIC STATION, ILOILO CITY

Principal Features of the Project:

The project is an Access Road Concreting of the PAGASA Radar and Synoptic Station, ILILO CITY

The work shall include, but are not limited to supply of the access road, all items related to complete the project and Concreting works.

The work shall include the furnishing of all materials, labor, tools, equipment, board-ups, technical supervision and other services, supply as identified, and accordance with the requirements of the approved plans and subject to the terms and condition of the contract documents.

SCOPE OF WORKS:

FOR ACCESS ROAD CONCETING

1. Site Clearing stake out work
2. Scriping and Back Filling Tampering using roller compactor
3. Gravel bedding
4. Installation of formwork)
5. Concrete Pouring
6. Cleaning.