Project Title : Construction of Cotabato Synoptic and River Basin Flood Forecasting Warning Center
Location :
Subject : BILL OF MATERIALS

ITEM	ITEM / DESCRIPTION	QTY.	UNIT	UNIT COST	ESTIMATED DIRECT COST (EDC) MATERIAL	LABOR	EQUIPMENT	DIRECT COST	INDIRECT COST (IC) OVERHEAD	CONTIGENCIES	MISCELLANEOUS	PROFIT	VAT-COMPONENT	TOTAL AMOUNT	UNIT COST
1	**GERERAL REQUIREMENTS:**														
	Bodega, Bunkhouse	1	lot												
	Mobilization	1	lot												0.00
	Scaffolding	1	lot												
First Floor															
2	**EARTH WORKS**														
	a. Backfilling + .30% compaction(17mx12mx.50m)+.30%)	132	cu.m												0.00
	b. Excavation of Foundation 0f Colunm & Wall Footing	83	cu.m												
	c. Soil poisoning (Termite X)	504	cu.m												
3	**STRUCTURAL WORKS**														
	a. Wall Footing Foundation														
	Cement	*26.00*	Bags												
	Sand	*2.00*	cu.m												0.00
	gravel bedding	*1.00*	cu.m												
	Crust gravel 3/4" class A	*4.00*	cu.m												
	RSB 12mm dia. X 6.0m	*25.00*	pcs												
	Tie wire #16	*4.00*	kg												
	b. Column Footing Foundation														
	Cement	*78*	Bags												
	Sand	*4*	cu.m												
	Gravel bedding, 100mm.thk.	*1*	cu.m												0.00
	Crust gravel 3/4" class A	*8*	cu.m												
	RSB 16mm dia. X 6.0m	*84*	pcs												
	Tie wire #16	10	kg												
	c. Tie Beam														
	Cement	85	Bags												
	Sand	5	cu.m												0.00
	Crust gravel 3/4" class A	9	cu.m												
	RSB 10mm dia. X 6.0m	94	pcs												
	RSB 16mm dia. X 6.0m	57	pcs												
	Tie wire #16	15	kg												
	d. Concrete Column														
	Cement	224	Bags												
	Sand	11	cu.m												0.00
	Crust gravel 3/4" class A	20	cu.m												
	RSB 10mm dia. X 6.0m	225	pcs												
	RSB 16mm dia. X 6.0m	167	pcs												
	Tie wire #16	42	kg												
	e. Rectangular Beam														
	Cement	*104*	Bags												
	Sand	*5*	cu.m												
	Crust gravel 3/4" class A	9	cu.m												
	RSB 10mm dia. X 6.0m	*152*	pcs												
	RSB 16mm dia. X 6.0m	*104*	pcs												0.00
	Tie wire #16	*15*	kg												
	g. Entrace Canopy														
	Cement	13	Bags												
	Sand	1	cu.m												
	Crust gravel 3/4" class A	1	cu.m												
	RSB 10mm dia. X 6.0m	24	pcs												
	Tie wire #16	2	kg												0.00

	h. OVERHANG SLAB Canopy			
	Cement	30	Bags	
	Sand	2	cu.m	
	Crust gravel 3/4" class A	2	cu.m	
	RSB 10mm dia. X 6.0m	24	pcs	
	Tie wire #16	2	kg	0.00
	i. Ground Flooring			
	Cement	210	Bags	
	Sand	11	cu.m	
	S1	10	cu.m	
	Crust gravel 3/4" class A	22	cu.m	
	RSB 10mm dia. X 6.0m	392	pcs	0.00
	Tie wire #16	55	kg	
	J. Concrete Roofing 1.00M wide, 5.00M length and 0.125M thk			
	Cement	5	bags	
	Sahara cement	5	packs	
	Sand	0.5	cum	
	Gravel	1	cum	
	Rebars, 12mm	30	pcs.	
	GI Tie wire, #16	3	kgs	
	Plywood, 12mmthk	2	pcs.	
	2" x 4" x 12' coco Lumber	300	bf	
	Assorted common Nails	4	kgs	0.00
	K. Concrete Window Canopy Dimension : 32.00LM x 0.60M @ 0.075m thk.			
	Cement	10	bags	
	Sand	0.5	cum	
	Gravel	1	cum	
	Sahara Cement	10	packs	
	Rebars, 12mm	39	pcs.	
	GI Tie Wire #16	2	kgs	
	Plywood, 12mm	5	pcs.	
	Coco Lumber, 2" x 2" x 12'	110	bf.	
	Assorted Common Wire Nail	6	kgs	
	Coco Lumber, 2" x 4" x 12'	450	bf.	
	Coco Lumber, 2" x 3" x 12'	60	bf.	0.00
4	**Masonry Works**			
	a. Masonry Works/Wall			
	#6CHB	*2,321*	pcs	
	Cement	*111*	Bags	
	Sand	*9*	cu.m	
	RSB 10mm dia. X 6.0m	*85*	pcs	
	Tie wire #16	*9*	kg	0.00
	b. Masonry Works/Partions			
	#4CHB	*3,157*	pcs	
	Cement	*152*	Bags	
	Sand	*13*	cu.m	
	RSB 10mm dia. X 6.0m	*123*	pcs	
	Tie wire #16	*12*	kg	0.00
	c. Plastering/Finishing			
	Cement	64	Bags	
	Sand	4	Cu.m	0.00
5	**Celing Works**			
	CMT T-Runner (main tee) @ 3.60M	60	pcs.	
	CMT Cross Tee, @ 1.20M	41	pcs.	
	CMT Cross Tee @ 0.60M	312	pcs.	
	Ceiling Hanger Channel @ 16ft	23	pcs.	
	CMT Wall Angle @ 3.00M	41	pcs.	
	Ceiling Boards,12mm x 0.60M x 1.2M	122	pcs.	
	Hanger Rod with accessores	133	sets	
	Ceiling Accessories	1	lot	0.00
6	**Tiles Works**			

	Granite Floor Tiles 60cm x 60cm	500	pcs													
	All Purpose Tile Adhesive @ 25kg/bag	255	Bags													
	ABC Grout 2 kg/pck	34	Packs													
	Ceramic C.R. Floor Tiles 30 x 30	180	pcs													
	Tiles Adhesive per(20kls)	76	Bags													
	Ceramic C.R. Wall Tiles 30 x 30	570	pcs													
	Tile Trim	10	pcs													
	Flooring Accessories	1	lot													0.00
7	***GROUND FLOOR DOOR***															
	Analuk Framed Glass Door (0.80M x 2.10M with installati	2	sets													
	Plastic Doors, 0.60M x 2.10M with plastic door jambs and	2	sets													
	Panel Door, 2.10M x 0.90M	3	pcs.													
	Panel Door, 2.10M x 0.90M w/ peep-in glass	1	pc													
	Panel Door, 2.10m x 0.80M	1	pc													
	Panel Door, 2.10M x 0.75M	1	pc													
	Wood Door Jambs, 2" x 5"	6	pcs.													
	Steel Door, 0.90M x 2.10M including steel door jamb and	1	sets													
	Loose Pin Hinges, 4" x 4"	9	pairs													
	Door Lockset	8	sets													0.00
8	***GROUND FLOOR WINDOW***															
	Aluminum Framed sliding Windows, 1.20M x 2.50M	4	sets													
	Aluminum Framed sliding Glass Windows, 1.20M x 1.40M	1	set													
	Aluminum Framed Sliding Glass Windows, 1.00M x 1.40M	1	set													
	Aluminum Framed Awning Type Window, 0.60M x 0.60M	2	sets													0.00
	Analuk Aluminum Framed Glass Windows with fixed glass and awning at bottom, 0.80M x 1.20M	1	set													
	2" x 4" Analuk Aluminum Framed Curtain Type Window w/ awning and tempered fixed glass (2.70M x 4.80M)	1	set													
9	**PLUMBING WORKS 1st Foor**															
	PVC PIPE ALASCO 4"Ø X 10' SERIES 1000	14	PCS.													
	PVC PIPE ALASCO 2"Ø X 10' SERIES 1000	12	PCS.													
	PVC WYE 4"Ø X 4"Ø	9	PCS.													
	PVC WYE 4"Ø X 2"Ø	13	PCS.													
	PVC TEE 4"Ø X 4"Ø	4	PCS.													
	PVC TEE 4"Ø X 2"Ø	6	PCS.													
	PVC ELBOW 4"Ø X 90°	14	PCS.													
	PVC ELBOW 4"Ø X 45°	9	PCS.													
	PVC WYE 2"Ø X 2"Ø	6	PCS.													
	PVC TEE 2"Ø X 2"Ø	16	PCS.													
	PVC ELBOW 2"Ø X 90°	21	PCS.													
	PVC ELBOW 2"Ø X 45°	11	PCS.													0.00
	PVC P TRAP 2"Ø	7	PCS.													
	PVC CLEAN OUT 4"Ø	4	PCS.													
10	**WATER LINE:**															
	PVC MOLDEX PIPE 3/4" X 10'	15	PCS.													
	PVC MOLDEX PIPE 1/2" X 10'	6	PCS.													
	PVC ELBOW 3/4" X 90°	9	PCS.													
	PVC ELBOW REDUCER 3/4 X 1/2	6	PCS.													
	PVC TEE 3/4"	7	PCS.													
	PVC TEE REDUCER 3/4 X 1/2	8	PCS.													
	PVC ELBOW 1/2" X 90°	8	PCS.													
	PVC ELBOW 1/2" X 90° ONE SIDE THREADED	14	PCS.													
	PVC MALE ADAPTOR 3/4"	6	PCS.													0.00
	PVC FEMALE ADAPTOR 1/2"	6	PCS.													
	GATE VALVE 3/4"	2	PCS.													
	TEFLON TAPE	5	PCS.													
11	***PAINTING GROUND FLOOR***															
	Latext Paint	6	pails													

	Enamel Paint	4	gals													
	Painting Colors	6	Lit													
	Paint Thinner	6	gals													
	Calsomine	20	kls													
	Sandpaper, #80	5	yards													
	Roller Brush 4" w/ Tray	4	pcs													0.00
	Paint Brush 2"	4	pcs													
11.1	**Speciality Works**															
	Curtain Wall, Tempered Glass, 12mm Thk.	1	lot													
	Glass Wall, Temperd Glass, 12mm	1	lot													
11.2	**Mechanical Works**															
	Booster Pump:1 HP: with metal mounting	1	lot													
Second Floor																
12	**STRUCTURAL WORKS**															
	a. Concrete Column															
	Cement	99	Bags													0.00
	Sand	5	cu.m													
	Crust gravel 3/4" class A	9	cu.m													
	RSB 10mm dia. X 6.0m	38	pcs													
	RSB 16mm dia. X 6.0m	49	pcs													
	Tie wire #16	9	kg													
	b. Rectangular Beam															
	Cement	103	Bags													
	Sand	6	cu.m													
	Crust gravel 3/4" class A	12	cu.m													
	RSB 10mm dia. X 6.0m	145	pcs													0.00
	RSB 16mm dia. X 6.0m	190	pcs													
	Tie wire #16	14	kg													
	c. Concrete Floor Slab															
	Cement	210	Bags													
	Sand	11	cu.m													
	Crust gravel 3/4" class A	21	cu.m													
	RSB 10mm dia. X 6.0m	392	pcs													0.00
	RSB 12mm dia. X 6.0m	392	pcs													
	Tie wire #16	15	kg													
	c. Masonry Works/Partions															
	#4CHB	1,784	pcs													
	Cement	27	Bags													
	Sand	2	cu.m													
	RSB 10mm dia. X 6.0m	72	pcs													0.00
	Tie wire #16	7	kg													
	d. Plastering/Finishing															
	Cement	64	Bags													0.00
	Sand	4	cu.m													
14	**Celing Works**															
	CMT - T Runner (main tee)@ 3.60m length	102	pcs.													
	CMT - Wall angle 3.60m length @ 3M Length	340	pcs.													
	CMT cross tee@ 0.60M length	102	pcs.													
	CMT cross tee@ 1.20M length	340	pcs.													
	CMT main tee self jointing butt joint	37	pcs.													
	CMT main tee to cross tee	68	pcs.													
	hanger /rods @.67M rod length and complete accessories	17	pcs.													
	Ceiling /Gypsun boards, @ 12mm thick X 1.20M x 2.40M	106	pcs.													
	ceiling Accessories	1	lot													0.00
12.1	**Concrete Floor Slab (Roofdeck)**															
	Cement	204	Bags													
	Sand	10	cu.m													
	Crust gravel 3/4" class A	20	cu.m													
	RSB 10mm dia. X 6.0m	392	pcs													

	RSB 12mm dia. X 6.0m	392	pcs													
	Tie wire #16	100	kg													0.00
13	**MASONRY WORKS**															
	a. Masonry Works/Wall															
	#6CHB	*2,321*	pcs													
	Cement	*111*	Bags													
	Sand	*9*	cu.m													
	RSB 10mm dia. X 6.0m	*85*	pcs													
	Tie wire #16	*9*	kg													0.00
	b. Masonry Works/Parapet															
	#6CHB	*641*	pcs													
	Cement	*31*	Bags													
	Sand	*3*	cu.m													0.00
	RSB 10mm dia. X 6.0m	*31*	pcs													
	Tie wire #16	*4*	kg													
15	**WATERPROOFING WORKS**															
	Waterproofing Membrane 4mm	28	rolls													
	Primer 20 liters per pail (1 coat)	5	pails													
	Structural Epoxy	11	gal/set													
	LPG w/Tank	5	tanks													0.00
15.1	***Roof deck concrete Tapping at .067mx10mx16m= 11.0cu.m.***															
	cement	94	bags													
	sand	6	cu.m													
	gravelets 1/2"	10	cu.m													
	wire mesh gages 10"x1.5mx3m	36	rolls													
	elastomeric paint	16	880													0.00
16	**Tiles Works**															
	Granite Floor Tiles 40 x 40	840	pcs													
	All Purpose Tile Adhesive @ 25kg/bag	255	Bags													
	ABC Grout 2 kg/pck	30	Packs													
	Ceramic C.R. Floor Tiles 30 x 30	180	pcs													
	ABC Grout 2 kg/pck	6	Packs													
	Ceramic C.R. Wall Tiles 30 x 30	570	pcs													
	Tiles Adhesive per(20kls)	76	Bags													
	ABC Grout 2 kg/pck	10	Packs													
	Tile Trim	10	pcs													
	Flooring Accessories	1	lot													0.00
17	***SECOND FLOOR/DOOR***															
	Panel Door, 2.10 x 0.90M	2	pcs													
	Panel door, 2.10 x 0.80M	2	pcs													
	Panel Door, 2.10M x 0.70m	1	pc													
	Plastic door, 0.60M x 2.10M with complete installation a	3	sets													
	Steel Door , 0.90M x 2.10M w/ complete accessories	1	set													
	Door Jambs, 2" x 5"	5	sets													0.00
	Loose Pin hinges, 4" x 4"	8	pairs													
	Door Locksets	8	sets													
18	***SECOND FLOOR/WINDOW***															
	ANALUK ALUMINUM WINDOW FRAME 1.20 M X 2.50 M	4	PCS													0.00
	ANALUK ALUMINUM WINDOW FRAME 1.20 M X 1.30 M	6	PCS													
	ANALUK ALUMINUM WINDOW FRAME (AWNING TYPE) 0.60 M X 0.6 M	3	PCS													
	ANALUK ALUMINUM WINDOW FRAME (AWNING TYPE) 1.750 M X 1.10 M	1	PC													
	ANALUK ALUMINUM WINDOW FRAME (AWNING TYPE) 3.350 M X 2.5 M	1	PC													
	Tempered Glass 1/2"X 0.30 M X 2.50 M	6	PCS													
19	**2ND FLOOR SANITARY:**															
	PVC PIPE ALASCO 4"Ø X 10' SERIES 1000	8	PCS.													
	PVC PIPE ALASCO 2"Ø X 10' SERIES 1000	9	PCS.													
	PVC WYE 4"Ø X 4"Ø	6	PCS.													
	PVC WYE 4"Ø X 2"Ø	11	PCS.													
	PVC TEE 4"Ø X 4"Ø	3	PCS.													

	PVC TEE 4"Ø X 2"Ø	4	PCS.													
	PVC ELBOW 4"Ø X 90°	11	PCS.													
	PVC ELBOW 4"Ø X 45°	7	PCS.													
	PVC WYE 2"Ø X 2"Ø	4	PCS.													0.00
	PVC TEE 2"Ø X 2"Ø	12	PCS.													
	PVC ELBOW 2"Ø X 90°	24	PCS.													
	PVC ELBOW 2"Ø X 45°	9	PCS.													
	PVC P TRAP 2"Ø	7	PCS.													
	PVC CLEAN OUT 4"Ø	2	PCS.													
	PVC COUPLING REDUCER 4"Ø	2	PCS.													
	NELTEX PVC CEMENT 400 CC	6	CAN													
20	**WATER LINE:**															
	PVC MOLDEX PIPE 3/4" X 10'	5	PCS.													
	PVC MOLDEX PIPE 1/2" X 10'	5	PCS.													
	PVC ELBOW 3/4" X 90°	6	PCS.													
	PVC ELBOW REDUCER 3/4 X 1/2	5	PCS.													
	PVC TEE 3/4"	4	PCS.													
	PVC TEE REDUCER 3/4 X 1/2	7	PCS.													
	PVC ELBOW 1/2" X 90°	7	PCS.													
	PVC ELBOW 1/2" X 90° ONE SIDE THREADED	11	PCS.													0.00
	PVC MALE ADAPTOR 3/4"	4	PCS.													
	PVC FEMALE ADAPTOR 1/2"	4	PCS.													
	GATE VALVE 3/4"	2	PCS.													
	TEFLON TAPE	5	PCS.													
	DOME STRAINER	4	PCS.													
21	**FIXTURE:**															
	WATER CLOSET/ COMPLETE FITTINGS	9	SETS													
	LAVATORY/ COMPLETE FITTINGS	7	SETS													
	URINAL/ COMPLETE FITTINGS	3	SETS													
	KITCHEN SINK/ COMPLETE FITTINGS	1	SET													
	SHOWER VALVE/SHOWER HEAD	3	SETS													
	FLOOR STRAINER	11	PCS													
	PVC Solvent @ 400ml/can	2	can													0.00
	Teflon Tape	6	rolls													
	Tissue Holder	9	PCS													
	Soap Holder	9	PCS													
22	**CIVIL WORKS**															
	a. Stairs, Railing															
	50mm x 50mm Tubular @ 1.2mm thk	3	pcs.													
	38mm BI Pipe, Gauge 1.20mm	4	pcs.													
	25mm x 50mm Tubular @ 1.20mm thk	5	pcs.													
	Plain Bar 14mm	7	pcs.													
	Welding Rod	10	kgs													
	Cutting Disc, 4" dia	9	pcs.													
	Grinding Disc, 4" dia	5	pcs.													
	Epoxy Primer Paint	1	gal													
	QDE Paint, Choco Brown	1	gal													
	Paint Thinner	1	gal													0.00
	Lacquer Thinner	1	gal													
	Assorted Painting accessories	1	lot													
	b. Column Footing															
	Cement	5	bags													
	Sand	1	cu.m													
	Crust gravel 3/4" class A	1	cu.m													
	RSB 12mm dia. X 6.0m	9	pcs													0.00
	Tie wire #16	1	kls													
	c. Column @.48cu.m															
	Cement	5	bags													
	Sand	1	cu.m.													
	Crust gravel 3/4" class A	1	cu.m													
	RSB 12mm dia. X 6.0m	10	pcs													0.00
	RSB 10mm dia. X 6.0m	14	pcs													
	Tie wire #16	1	kls													
	d. lentel BEAM @ landing @.36 cu.m.															

	Cement	4.0	bags													
	Sand	0.5	cu.m.													
	Crust gravel 3/4" class A	0.5	cu.m													
	RSB 12mm dia. X 6.0m	5.0	pcs													0.00
	RSB 10mm dia. X 6.0m	9.0	pcs													
	Tie wire #16	2.0	kgs													
	e. Slab for stair landing @.5 cu.m.															
	Cement	5.0	bags													
	Sand	1.0	cu.m.													
	Crust gravel 3/4" class A	1.0	cu.m													
	RSB 10mm dia. X 6.0m	36.0	pcs													0.00
	Tie wire #16	2.0	kgs													
	f. Stair steps @.81cu.m.															
	Cement	8.0	bags													
	Sand	1.0	cu.m													
	Crust gravel 3/4" class A	1.0	cu.m													
	RSB 10mm dia. X 6.0m	16.0	pcs													
	RSB 12mm dia. X 6.0m	4.0	pcs													0.00
	Tie wire #16	2.0	kgs													
23	**For outside steel stair**															
	g. Excavation															
	a. column footing excavation	4.0	cu.m.													
	For Steel Stair at exit C-Channel 10" x 1/4" x 20'	4.0	pcs													0.00
	b. stail railing															
	2" x 1/2"x 20' steel Tubular	15.0	pcs													
	c. Column post/G.I. pipes															
	3' dia. G.I. pipes sched 60	4.0	pcs													
	d. For chekered steel plates for steps and landing															
	1/8" x 4' x 8' checkered steel plates	3.0	pcs													
	e. for footing/column pedistal of G.I. post															
	Cement	5.0	bags													0.00
	sand	1.0	cu.m.													
	Crust gravel 3/4" class A	2.0	cu.m													
24	**Outside railings (31 LM)**															
	BI Tubular 50mm x 50mm @ 1.20mm thk	6	pcs.													
	BI Tubular 25mm x 50mm @ 1.20mm thk	27	pcs.													
	Welding Rod	10	kgs													
	Epoxy Paint Primer	2	gals													
	QDE Paint Choco Brown	3	gals													0.00
	Cutting Disc, 4"	5	pcs.													
	Grinding Disc, 4"	5	pcs.													
	Paint Thinner	2	gal													
	Lacquer thinner	2	gal													
25	**PAINTING SECOND FLOOR**															
	Latext Paint	7	tins													
	Enamel Paint	5	gals													
	Painting Colors	6	Lit													0.00
	Paint Thinner	6	gals													
	Calsomine	20	kls													
	Sand Papers 108	5	yards													
	Roller Brush 4" w/ Tray	4	pcs													
	Paint Brush 2"	4	pcs													
26	***SEPTIC VAULT (2MX3MX2M)***															
	CHB 4"	133	pcs													
	Cement	*39*	Bags													
	Sand	*3*	cu.m													
	Crust gravel 3/4" class A	*2*	cu.m													0.00
	RSB 10mm dia. X 6.0m	*72*	pcs													
	Tie wire #16	*10*	kg													
27	***ELECTRICAL SYSTEM***															

	Panel Board w/ 1-mains 150 AT 2P 1Ø 240VAC 85 KAIC, Bolt-On, 6pcs-15Amp, 7pcs-20Amp, 8 pcs-30Amp 6pcs-40Amp. All Sq. D. type CB	1	set												
	150 AMP sq. D CB w/enclosure NEMA4X	1	set												0.00
	150Amp Sq D. CB w/ enclosure, NEMA 3R	1	set												
	2" Ø Service Entrance Cap	1	pc												
	3.5mm^2,THHN/THWN wire, black, @150mtrs/roll	10	rolls												
	5.5mm^2,THHN/THWN wire, black, @ 150mtrs/roll	1	roll												
	8.0mm^2,THHN/THWN wire,black @ 100mtrs/roll	4	rolls												
	3.5mm^2, TW wire, green @150mtrs/roll	1/2	roll												
	5.5mm^2, TW wire, green, @ 150mtrs/roll	4	rolls												
	50.0mm^2,THHN/THWN wire, black	100	mtrs												
	30.0mm^2,TW wire, green	50	mtrs												
	GI wire #16	5	kgs												
	3/4" Ø PVC pipe, " standard" orange, 8'/length	264	length												
	1" Ø PVC pipe, " standard" orange, 8'/length	66	length												
	2" Ø PVC pipe, " standard" orange, '/length	38	length												
	2" Ø RSC pipe, 8'/length	3	length												
	Locknut & Bushing for 3/4" Ø PVC,"standard"	352	pcs												
	Locknut & Bushing for 1" Ø PVC,"standard"	14	pcs												
	Locknut & Bushing for 2" Ø PVC,"standard"	2	pcs												
	Locknut & Bushing for 2" Ø RSC pipe	2	pcs												
	90° Long Elbow for 2" Ø RSC pipe	2	pcs												
	90° Long Elbow for 2" Ø PVC,"standard"	2	pcs												
	90° Long Elbow for 3/4" Ø PVC,"standard"	74	pcs												
	Junction Box (Octagon) 2"x2"x2" (plastic)	63	pcs												
	JB(Octagon) -Plate Cover 2"x2"x2"(plastic)	55	pcs												
	Utiliy Box 2"x2"x4" (plastic)	74	pcs												
	Single Pole Switch	32	pcs												
	Three Way Switch	2	pcs												
	Convinience Outlet	70	pcs												
	Range & Pump Outlet	2	pcs												
	Plate Cover (single)	22	pcs												
	Plate Cover (double)	40	pcs												
	Plate Cover (triple)	4	pcs												
	ACU Outlet w/ Plate Cover	3	pcs												
	Lamp Socket (Plastic)	64	pcs												
	Surface Type LED Lamp	64	pcs												
	Spool Insulator Assembly (3 spool/set)	1	set												
28	**Electric Service Entrance Post & 3 Manholes(pull box) w/ cover**														
	Cement	15	Bags												
	sand	1	cu.m												0.00
	Crust gravel 3/4" class A	2	cu.m												
	RSB 10mm dia. X 6.0m	15	pcs												
	RSB 12mm dia. X 6.0m	12	pcs												
	Tie wire #16	3	kg												
29	**Flag Pole**														
	Cement	6	Bags												
	sand	1	cu.m												
	Crust gravel 3/4" class A	1	cu.m												
	RSB 10mm dia. X 6.0m	1	pcs												
	RSB 12mm dia. X 6.0m	5	pcs												
	Tie wire #16	1	kg												0.00
	G.I. Pipe 2" Dia.	1	pcs												

0.00
0.00